

10-6-71
RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
500 INSURANCE BUILDING
212 NORTH MARKET
WICHITA, KANSAS 67202

OCT 6 1971 FORM CP-1

~~RECEIVED
STATE CORPORATION COMMISSION
OCT 6 1971
CONSERVATION DIVISION
Wichita, Kansas
10-4-71~~

WELL PLUGGING APPLICATION FORM
File One Copy

15-147-00511-00-00

Lease Owner Cities Service Oil Company

Address Box 553 Russell, Kansas 67665

Lease (Farm Name) Bailey "A" Well No. 3

Well Location 1650' FNL & 330' FEL Sec. 30 Twp. 5S Rge. 20 (E) (W) X

County Phillips Field Name (If Any) Ray Pool

Total Depth 3665' Oil Well Gas Well Input Well SWD Well D & A

Well Log filed with application Yes or Well Log filed with Plugging Supervisor

Date and hour plugging is desired to begin 10-11-71 10:00 A.M.

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of company representative in charge of plugging operations W. E. Anderson

Address Box 277 Logan, Kansas 67646


Plugging Contractor Knight Casing Pulling Co., Inc. License No.

Address P.O.Box 405 Chase, Kansas 67524

Invoice covering assessment for plugging this well should be sent to E. W. Peterman

Address Box 553 Russell, Kansas 67665

and payment will be guaranteed by applicant.

Signed:  E. W. Peterman
Applicant or Acting Agent

Date: October 1, 1971

15-47-00511-00-00

CONSERVATION DIVISION
Wichita, Kansas

Company Cities Service Oil Co. Well No. 5 Farm Bailey
 Location 990' North and 330' West of E/4 Corner Sec. 30 T. 5 R. 20W
 Elevation 2205 (2205 Gr.) County Phillips State Kansas
 Drlg. Comm. December 5, 1949 Contractor R. W. Rine Drilling Company
 Drlg. Comp. December 16, 1949 Acid None
 T. D. 3665' Initial Prod. Physical Potential: 65 oil, 44% water, 24 hrs. (2-6-50)
 P. D. 3647'

CASING RECORD:

8-5/8" @ 207' cem. 250 sx cement
 5-1/2" @ 3665' cem. 150 sx cement

Top Lansing 3390'
 Top Reagan 3642'
 Penetration 23'
 Total Depth 3665'

FORMATION RECORD:

sand & clay 0-130
 shale 207
 shale & sand 1743
 anhydrite 1780
 shale & shells 2805
 lime & shale 3105
 lime 3627
 cored: sandy shale & shaly sand, rec. 4 1/2' 3632
 cored: sandy shale & shaly sand, rec. 5' 3637
 cored: sandy shale & shaly sand, rec. 3 1/2' 3642
 cored: sand, rec. 7' 3649
 sand 3665

Drilled cement to 3658 SIM.
 Perf. 12 shots 3641-43, 280' fluid in 10 mins.
 510' fluid in 20 mins.
 1115' fluid in 40 mins.
 2020' fluid in 1 hr. 40 mins.
 Perf. 8 shots 3649-51
 2330' fluid in 2 hrs. 25 mins.
 2650' fluid in 3 1/2 hrs. (1050' oil and 1600' water)
 Set retainer at 3619 and squeezed with 55 sx cement; 45 sx through perforations at 2500#.

3665 RFD = 3665 SIM

Drilled cement to 3647 SIM.
 Perf. 12 shots 3641-43
 2 gals. oil & tr. wtr. in 25 mins.
 Perf. 6 shots 3643-44
 130' fluid in 40 mins.
 230' fluid in 1 hr. 10 mins.
 450' fluid in 1 1/2 hrs.
 1020' fluid in 3 hrs.
 2138' fluid in 8 hrs.
 2519' fluid (1400' oil and 1119' wtr.) in 17 hrs.

12-30-49 Papd. 91 oil, 44 wtr., 14 hrs.

SYFO: 500' 0°
 1000' 0°
 1500' 0°
 2000' 0°
 2500' 1°

7-7/8" rotary hole.

Handwritten notes:
 12-31-49
 12-31-49
 12-31-49
 12-31-49

State of Kansas



15-147-00511-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

October 6, 1971

RECEIVED
STATE CORPORATION COMMISSION
DEC 6 1971
CONSERVATION DIVISION
Wichita, Kansas

12-6-71

WELL PLUGGING AUTHORITY

Well No.	3
Lease	Bailey "A"
Description	NE SE NE 30-5-20W
County	Phillips
Total Depth	3665
Plugging Contractor	Knight Casing Pulling Co. Inc.

Cities Service Oil Company
Box 553
Russell, Kansas 67665

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Very truly yours,

J. Lewis Brock
J. Lewis Brock, Administrator

Mr. Leo Massey Box 582 Hays, Kansas

is hereby assigned to supervise the plugging of the above named well.