

15-183-01008-00-00

By 11w
10-5-11w

KANSAS STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

RECEIVED
DEC 30 1936
12-30-36
80

WELL PLUGGING APPLICATION

Well Location C. NE SW Sec. 10 Twp. 11 Rge. 5 (W)

Field Name (if any) None County Smith

Lease (Farm Name) Meyer Well No. 1

Was well log filed with application? Yes If not, explain circumstances and give available data (Use an additional sheet if necessary)

Verbal application made by driller when Siliceous was cored and found dry

Will the plugging of the well be done in accordance with the Rules and Regulations of the Kansas State Corporation Commission? Yes If not, explain fully exceptions desired (Use additional sheet if necessary)

Hole pumped full of rotary mud. Placed 15 sacks of cement at bottom of 10" surface casing. Placed 10 sacks of cement in surface casing and welded top of casing

Date plugging is desired to begin December 2, 1936

Name of the person on the lease in charge of well for owner

C. P. Baker Address Downs, Kansas

PLUGGING
FILE 10-11-18W
PAGE 22
30

Name of well owner or acting agent Helmerich & Payne, Inc.

Address 916 Philtower Building, Tulsa, Oklahoma

To whom should invoice covering assessment for plugging well be sent?

Helmerich & Payne, Inc. Address Tulsa, Oklahoma

E. M. Toleland
Operator or Acting Agent

Date December 28, 1936

Meyer #1
Center of Northeast Quarter of Southwest Quarter
Section 10-5S-11W
Smith County, Kansas
Helmerich & Payne, Inc.

Surface sand	0	210
Shale and shells	210	690
Pyrites and shale	690	705
Shale and shells	705	750
Sand and shale	750	900
Shale and shells	900	1015
Shale	1015	1195
Shale and shells	1195	1305
Sandy shale	1305	1400
Sand and shale	1400	1405
Lime and shale	1405	1565
Lime	1565	1630
Lime and shale	1630	1660
Lime	1660	1680
Lime and shale and red rock	1680	1695
Lime and shale	1695	1925
Lime	1925	2040
Lime and shale	2040	2610
Lime	2610	2620
Lime and shale	2620	2705
Lime	2705	2770
Lime and shale	2770	2920
Lime	2920	3070
Lime and shale	3070	3115
Lime	3115	3290
Lime and shale	3290	3590
Chat	3590	3635
Chat and lime	3635	3650
Chat	3650	3655
Lime	3655	4080
Lime and shale	4080	4105
Lime	4105	4135
Shale and lime	4135	4153
Lime (cored Siliceous)	4153	4161
Total Depth	4161	

10" Surface casing
cemented at 210 feet.

10 (11 1510)
72 20

STATE OF OKLAHOMA)
 - ss
COUNTY OF TULSA)

I hereby affirm that the above and foregoing is a true and correct copy of the log of our Meyer #1, located in the Center of the Northeast Quarter of the Southwest Quarter of Section 10, Township 5 South, Range 11 West, Smith County, Kansas.

HELMERICH & PAYNE, INC.

By _____
Secretary

Subscribed and sworn to before me, a Notary Public, this _____ day of December, 1936.

My commission expires
July 22, 1939.

Notary Public

HOMER HOCH, CHAIRMAN
JESSE W. GREENLEAF
ERNEST W. BLINCOE
COMMISSIONERS

PHONES 2-0488—L. D. 78



C. H. BENSON, SECRETARY
STATE CAPITOL
TOPEKA, KANSAS

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

December 3, 1936.

DIRECTOR
T. A. MORGAN, WICHITA
OIL ADVISORY COMMITTEE
RALPH J. PRYOR, CHAIRMAN,
WICHITA
WALTER S. FEES, IOLA
E. W. PYLE, WICHITA
LEE SCOTT, WICHITA
H. M. WILLIAMS, WICHITA
MARVIN LEE, SECRETARY AND
TECHNICAL ADVISER

IN REPLY PLEASE
REFER TO THIS
SUBJECT

15-183-01008-00-00

Well No. 1
Farm Name Myers
Description SW 10-11-5W
County Smith
File 72-30

Helmerich & Payne, Inc.,
916 Philtower Bldg.,
Tulsa, Oklahoma.

Dear Sirs:

This letter is your permit to plug
the above subject well, in accordance
with the Rules and Regulations of the
STATE CORPORATION COMMISSION.

Yours very truly,

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

T. A. MORGAN, Director

TC:ha By
Notice C. T. Alexander
Great Bend, Kansas