

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20943-00-01  
Spot: NW Sec/Twnshp/Rge: 27-33S-34W  
3910 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: ETZOLD UNIT Well #: 5-2  
County: SEWARD Total Vertical Depth: 6410 feet

Operator License No.: 4549  
Op Name: ANADARKO PETROLEUM CORPORATI  
Address: 1201 LAKE ROBBINS DRIVE  
THE WOODLANDS, TX 77380

PROD Size: 5.5 feet: 6409 WITH 150 SX CMT  
SURF Size: 8.625 feet: 1640 WITH 775 SX CMT

#208<sup>33</sup>

Well Type: EOR UIC Docket No: E24960.8 Date/Time to Plug: 11/08/2004 9:00 AM  
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE  
Proposal Rcvd. from: RICKY Company: EAGLE WELL SERVICE Phone: (620) 624-1904

Proposed Plugging Method: PUMP 200# HULLS & 30 SX CMT. PLUG AT 1700' WITH 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: PARTIAL  
Date/Time Plugging Completed: 11/09/2004 11:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 6372'. PUMPED 300# HULLS WITH 30 SX CMT. DISPLACE WITH MUD. PRESSURE 5 1/2" TO 800 PSIG. 1ST PLUG PULL OUT OF HOLE TO 1700'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 550'. SDON 11/9/04: LOAD HOLE WITH MUD & PUMP 50 SX CMT. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 15 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
6262	6302		

RECEIVED  
NOV 24 2004  
KCC WICHITA

Remarks: USED CLASS H CEMENT BY EAGLE WELL SERVICE. RECOVERED 1780' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PARTIAL  
(TECHNICIAN)

INVOICED  
DATE 11.29.04  
INV. NO. 2005060849

Form CR 275