

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21149-00-00
Spot: W2SEWSE Sec/Twnshp/Rge: 34-29S-34W
1385 feet from S Section Line, 1800 feet from E Section Line
Lease Name: MLP PAULINE MURPHY Well #: 1-34
County: HASKELL Total Vertical Depth: 5575 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: PO BOX 18496 6200 N WESTERN AVE.
OKLAHOMA CITY, OK 73154

PROD Size: 5.5 feet: 5574 WITH 375S X CMT
SURF Size: 8.625 feet: 1830 WITH 675 SX CMT

#181¹⁹

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/10/2004 2:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RANDY GRAYSON Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: MUX & PUMP 400# COTTON SEED HULLS, MIX & PUMP 25 SX CMT W/100# HULLS, DISPLACE W/75 BBL, FSW, MIX & PUMP 110 SX CMT, PRESSURE TO 1000 PSIG, WAIT 20 MINUTES, TOP OFF IF NECESSARY. TIE ONTO ANNULUS, MIX & PUMP 50 SX CMT. RDMO. WELD ON CAP CLEAN UP LOCATION.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2004 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

CEMENT CIRCULATED ON PORT COLLAR @ HUGOTON/COUNCIL GROVE. PBTD 5537'. PUMP 500# HULLS MIXED IN 50 SX CMT TO PLUG BOTTOM. PUMP 70 BBL MUD SPACER TO 1800'. PUMP 140 SX CMT FROM 1800' TO SURFACE INSIDE 5 1/2" CASING. PRESSURE TO 500 PSIG & SHUT IN. PUMP 10 SX CMT DOWN BACKSIDE. PRESSURE TO 300 PSIG & SHUT IN.

Perfs:


Top	Bot	Thru	Comments
5258	5362		
4732	4752		

RECEIVED
NOV. 24 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed Jim Holland PART II
(TECHNICIAN)

INVOICE
DATE 11-29-04
INV. NO. 2005060850

Form CP-2/B