

TQ:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20841-00-01
Spot: NWNE Sec/Twnshp/Rge: 27-33S-32W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease Name: ARKALON Well #: 1-27
County: SEWARD Total Vertical Depth: 2711 feet

Operator License No.: 7457
Op Name: ELDER & VAUGHN INC
Address: PO BOX 18938
OKLAHOMA CITY, OK 73118

CIBP Size: feet: 2461
PROD Size: 4.5 feet: 2650 WITH 150 SX CMT
SURF Size: 8.625 feet: 1557 CIRCULATED

48"

Well Type: ~~Oil~~ Gas *JA* UIC Docket No: Date/Time to Plug: 11/03/2004 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS WITH 20 SX CMT. PLUG AT 1600' WITH 50 SX CMT. PLUG AT 500' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/03/2004 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 200# HULLS & 20 SX CMT. DISPLACE TO BOTTOM WITH MUD. PRESSURE TO 500 PSIG & SHUT IN. 1ST PLUG PULL OUT OF HOLE WITH 1600'. LOAD HOLE & PUMP 50 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 500'. LOAD HOLE WITH MUD & PUMP 30 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2492	2504		
2480	2490		
2452	2462		
2451	2461		
2420	2426		
2419	2425		

RECEIVED
NOV 24 2004
KCC WICHITA

RECEIVED
NOV 15 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2100' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
NOV 10 2004
KCC Dodge City

Signed Jim Holland PART II
(TECHNICIAN)

INVOICED
DATE 11-29-04
INV. NO. 2005060853

Form CP-2/3