

15-147-00962-00 00

11-9 4-041826

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 05-30-42

SW SE SE /4 SEC. 30 , 05 S, 20 W
330 feet from S section line
990 feet from E section line

Operator license# 5447

Lease: States A Well # 1

Operator: OXY USA, Inc.

County: Phillips 118.75

Address: P.O. Box 300
Tulsa, Oklahoma 74102-0300

Well total depth 3654 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 162 feet
w/125% sxs.cmt.

Aband. oil well X, Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Halliburton Cementing, Inc. License# _____

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 9 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3646' w/100 sxs.
Open hole.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 11:00 A.M., Day: 9, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. Install 2" riser to surface. Rigged up H.L.S. & perf at 1165' and 1810' with 2 spf. MIRU Murfin Drilling, RIH with 2 3/8" tubing. Open ended to 3600' Pumped 65 sxs MIDCON 2 with 2% CC and 300# cottonseed hulls. Pulled 48 joints to 2100'. Pumped 65 sxs cement & 200# hulls. Pulled tubing to 600'. Pumped 30 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 5 1/2" casing and pumped 20 sxs cement. Max. P.S.I. 500#. S.I.P. 300#. Hooked up to 8 5/8" casing and pumped 50 sxs MIDCON 2 cement with 2% CC and 100# hulls. Rig down. Total cement used 230 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD _____ Anhy.plug: YES X NO _____
Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING X, CASING _____ Elevation: 2240 K.B. _____

I did[X] / did not[] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED
DATE JAN 10 1997
INV. NO. 47318

1-10-97