

11-12  
4-041837

15-147-00517-00-00

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 09-06-49

NE SE SW \_\_\_\_\_ / 4 SEC. 30, 05 S, 20 W  
990 feet from S section line  
2970 feet from E section line

Operator license# 5447

Lease: States B Well # 5

Operator: OXY USA, Inc.

County: Phillips 118.33

Address: P.O. Box 300  
Tulsa, Oklahoma 74102-0300

Well total depth 3641 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 222 feet  
w/250 sxs.cmt.

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Halliburton Cementing, Inc. License# \_\_\_\_\_

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00 A.M. Day: 12 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3633' w/150 sxs.  
Open hole.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[ ], Part[  ], None[ ]

Completed: Hour: 9:30 A.M., Day: 12, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. Install 2" riser to surface. Rigged up H.L.S. & perf at 1145' and 1790' with 2 spf. MIRU Murfin Drilling, RIH with 2 3/8" tubing. Open ended to 3600'. Pumped 65 sxs MIDCON 2 with 2% CC and 300# cottonseed hulls. Pulled 48 jts. to 2100'. Pumped 65 sxs cement & 200# hulls. Pulled tubing to 600'. Pumped 30 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 5 1/2" casing and pumped 25 sxs cement. Max. P.S.I. 500#. S.I.P. 500#. Hooked up to 8 5/8" casing and pumped 50 sxs MIDCON 2 cement with 2% CC and 100# hulls. Max. P.S.I. 300#. S.I.P. 200#. Total cement used 240 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD  BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES  CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES  NO \_\_\_\_\_  
Plugged through TUBING  CASING \_\_\_\_\_ Elevation: 2218 K.B.

I did  / did not  observe the plugging.

Dennis L. Hamel  
(agent)

Form CP-2/3

INVOICED  
DATE JAN 10 1997  
NV. NO. 47307

1-10-97