

11-8 4-041830 15-147-00513-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 03-24-49

NE SE SE /4 SEC. 30 , 05 S, 20 W
990 feet from S section line
330 feet from E section line

Operator license# 5447

Lease: States A Well # 5

Operator: OXY USA, Inc.

County: Phillips 119.27

Address: P.O. Box 300
Tulsa, Oklahoma 74102-0300

Well total depth 3670 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 215 feet
w/250 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton Cementing, Inc. License# -

Address: Hays, Kansas 67601 1-10-97

Company to plug at: Hour: 7:30A.M. Day: 8 Month: November Year: 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3670' w/175 sxs.
Open hole. Perf. 3612' - 3616' - 3624' - 3632' - 3632' - 3635'.
PBTB 3636'.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 8:45 A.M., Day: 8, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. Install 2" riser to surface. Rigged up H.L.S. & perf at 1140' and 1790' with 2 spf. MIRU Murfin Drilling, RTH with 2 3/8" tubing. Open ended to 3600' Pumped 65 sxs MIDCON 2 with 2% CC and 300# cottonseed hulls. Pulled 48 joints to 2100'. Pumped 65 sxs cement & 200# hulls. Pulled tubing to 600'. Pumped 20 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 5 1/2" casing and pumped 25 sxs cement. Max. P.S.I. 500#. S.I.P. 300#. Hooked up to 8 5/8" casing and pumped 50 sxs MIDCON 2 cement with 2% CC and 100# hulls. Max. P.S.I. 300#. S.I.P. 200#. Total cement used 245 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING X, CASING. Elevation: 2216 G.L.
Anhy.plug: YES X NO
Dakota plug: YES X, NO

I did[X] / did not[] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED
DATE JAN 10 1997
INV. NO. 47314