

5-11-88 15-147-00999-00-00

6 040892

API NUMBER 15- 5-10-42

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SEC. 30, T 5, S, R 20 W/
330 feet from S section line
1650 feet from ~~W~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447
Operator: Cities Service Oil and Gas
Name & Address: 3545 NW 58th
Oklahoma City, Ok. 73112

Lease Name States B Well # 1
County Phillips 119.99
Well Total Depth 3692 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 155' w/125 sks

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement License Number

Address Russell, Ks.

Company to plug at: Hour: 8:00AM Day: 11 Month: May Year: 19 88

Plugging proposal received from Phillip Pringle

(company name) Cities Service (phone)

were: 5 1/2" casing set at 3675' w/100 sks cement. Perfs at 3642' to 53'.

Perf casing at 1780' and 1080' w/4 S.P.F.

Ordered 325 sks 65/35 Poz 10% Gel w/1/2# F.C. plus 5 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 9:50AM Day: 11 Month: May Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 250 sks cement w/1/2# F.C. plus 5 sks Hulls

mixed in cement. Max Psi 1000# Shut in 500#. Pumped in 8 5/8" casing 75 sks cement

w/1/2# F.C. Max Psi 300# Shut in 200#.

RECEIVED
STATE CORPORATION COMMISSION
7-6-88
JUL 6 1988

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-7-88

INV. NO. 21207
5-11

Signed Dennis L. Hamel (TECHNICIAN)

Dennis L. Hamel

AUG 3 1988