

4-041836 13-147-60602-00-00

11-5

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 11-02-46

S2 NW SW /4 SEC. 30 , 05 S, 20 W
1650 feet from S section line
4620 feet from E section line

Operator license# 5447

Lease: States B Well # 4

Operator: OXY USA, Inc.

County: Phillips

Address: P.O. Box 300
Tulsa, Oklahoma 74102-0300

Well total depth 3678 ^{119.53} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 196 feet
w/250 sxs.cmt.

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Halliburton Cementing, Inc. License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 12:00 P.M. Day: 5 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3675' w/150 sxs.
Open hole.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 2:00 P.M., Day: 5, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. Install 2" riser to surface. Rigged up H.L.S. & perf at 1175' and 1810' with 2 spf. MIRU Murfin Drilling, RIH with 2 3/8" tubing. Open ended to 3610'. Pumped 45 sxs MIDCON 2 with 2% CC and 300# cottonseed hulls. Pulled to 2610'. Pumped 45 sxs cement & 100# hulls. Pulled tubing to 1610'. Pumped 45 sxs cement with 100 # hulls. Pulled to 600' and pumped 35 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 5 1/2" casing and pumped 25 sxs cement. Max. P.S.I. 500#. S.I.P. 375#. Hooked up to 8 5/8" casing and pumped 60 sxs MIDCON 2 cement with 2% CC and 100# hulls. Max. P.S.I. 50#.. S.I.P. 50#. Total cement used 260 sxs.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD _____ Anhy.plug: YES NO _____
Bottom plug(in place): YES , CALC _____, NO _____ Dakota plug: YES , NO _____
Plugged through TUBING , CASING _____ Elevation: 2248 K.B.

I did / did not observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

DATE JAN 10 1997

INV. NO. 47308

1-10-97