

11-5 4-041834 15-147-00600-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 08-05-46

SW SW SW /4 SEC. 30 , 05 S, 20 W
330 feet from S section line
4950 feet from E section line

Operator license# 5447

Lease: States B Well # 2

Operator: OXY USA, Inc.

County: Phillips 119.37

Address: P.O. Box 300
Tulsa, Oklahoma 74102-0300

Well total depth 3673 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 197 feet
w/200 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton Cementing, Inc. License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 3:00P.M. Day: 5 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3670' w/150 sxs.
Open hole.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 6:30 P.M., Day: 5, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. Install 2" riser to surface. Rigged up H.L.S. & perf at 1165' and 1800' with 2 spf. MIRU Murfin Drilling, RIH with 2 3/8" tubing. Open ended to 3630'. Pumped 45 sxs MIDCON 2 with 2% CC and 300# cottonseed hulls. Pulled to 2630'. Pumped 45 sxs cement & 200# hulls. Pulled tubing to 1630'. Pumped 45 sxs cement with 100 # hulls. Pulled to 630' and pumped 45 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 5 1/2" casing and pumped 20 sxs cement. Max. P.S.I. 300#. S.I.P. 250#. Hooked up to 8 5/8" casing and pumped 45 sxs MIDCON 2 cement with 2% CC and 100# hulls. Max. P.S.I. 50#. S.I.P. 50#. Total cement used 245 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING X, CASING. Elevation: 2248 K.B.
Anhy.plug: YES X NO
Dakota plug: YES X, NO

I did/did not observe the plugging.

INVOICED

DATE JAN 10 1997

NV. NO. 47310

Dennis L. Hamel (agent)