

11-8 4-041827 15-147-00596-00-00

TO:

API Number: 15- - 09-06-42

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

SW SW SE /4 SEC. 30 , 05 S, 20 W  
330 feet from S section line  
2310 feet from E section line

Operator license# 5447

Lease: States A Well # 2

Operator: OXY USA, Inc.

County: Phillips 118.13

Address: P.O. Box 300  
Tulsa, Oklahoma 74102-0300

Well total depth 3635 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4 Inch @ 164 feet  
w/125 sxs.cmt.

Aband. oil well  , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Halliburton Cementing, Inc. License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 12:00P.M. Day: 8 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 7" casing set at 3629' w/125 sxs.  
Open hole.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 2:30 P.M., Day: 8, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 7" to 10 3/4" casing. Install 2" riser to surface. Rigged up H.L.S. & perf at 1155' and 1800' with 2 spf. MIRU Murfin Drilling, RIH with 2 3/8" tubing. Open ended to 3610' Pumped 105 sxs MIDCON 2 with 2% CC and 300# cottonseed hulls. Pulled 48 joints to 2100'. Pumped 105 sxs cement & 200# hulls. Pulled tubing to 600'. Pumped 50 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 7" casing and pumped 25 sxs cement. Max. P.S.I. 500#. S.I.P. 200#. Hooked up to 8 5/8" casing and pumped 50 sxs MIDCON 2 cement with 2% CC and 100# hulls. Max. P.S.I. 200#. S.I.P. 50#. Total cement used 335 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD  BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES  , CALC \_\_\_\_\_ , NO \_\_\_\_\_ Dakota plug: YES  , NO \_\_\_\_\_  
Plugged through TUBING  , CASING \_\_\_\_\_ . Elevation: 2226 K.B.

I did observe the plugging.

INVOICED

DATE JAN 10 1997

INV. NO. 47317

Dennis L. Hamel  
(agent)