

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03477-00-01
Spot: SENWNW Sec/Twnshp/Rge: 24-11S-17W
4290 feet from S Section Line, 4290 feet from E Section Line
Lease Name: COLAHAN A Well #: 29
County: ELLIS Total Vertical Depth: 3485 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

L1 Size: 5.5 feet: 3527 w/100 sxs cmt
PROD Size: 7 feet: 3485 w/150 sxs cmt
SURF Size: 9.625 feet: 1120 w/600 sxs cmt

113²⁴

Well Type: SWD UIC Docket No: D09378.0 Date/Time to Plug: 11/22/2004 9:30 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9167

Proposed Plugging Method: Ordered out 450 sxs 60/40 pozmix - 10% gel - 500# hulls.
MIT failed 10-21-2004. Casing full of iron sulfide.
Drilled out to 1050' - could not drill any deeper - decided to P&A.
Emergency plug with rig over the hole.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/22/2004 12:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Tied onto 9 5/8" - mixed and pumped 50 sxs cement.
Max. P.S.I. 300#. S.I.P. 100#.
Switched over to 7" - pumped 50 sxs cement.
Max. P.S.I. 300#. S.I.P. 50#.
TIH with tubing to 1020' - circulated cement with 115 sxs cement.
POOH. Swaged onto 5 1/2" - pumped 100 sxs cement.
Topped with 80 sxs cement with 500# hulls.
Max. P.S.I. 500#. S.I.P. 100#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 11-29-04
TEL NO. 2005060858

NOV 23 2004

CITIES SERVICE OIL COMPANY #29 COLAHAN A 24-11-17W 34
SE NW NW


Contr. _____ ELLIS County

E 1919 Comm. 7-1-50 Comp. 8-1-50 IP 222 BOPD

Tops	Depth	Datum
HEEB	3071	
LANS	3130	-1211
SIMP SH	3391	-1472
ARB	3412	-1493
T.D.	3485	-1566

Casing
 9" 1120 CO 3479
 7" 3485 PERF 3452-3462:
 PMP 94 B0/5 HRS

BEMIS-SHUTTS POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

WADICEN