

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19036-00-00
Spot: NESWNE Sec/Twnshp/Rge: 6-14S-19W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: IRVIN Well #: 2
County: ELLIS Total Vertical Depth: 3906 feet

Operator License No.: 33069
Op Name: ENCORE OPERATING COMPANY
Address: P. O. BOX 27710
DENVER, CO 80227

PROD Size: 6 feet: 3888 250 SX CMT
SURF Size: 8.625 feet: 179 150 SX CMT

126⁹⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/22/2004 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ROLAND NYP Company: ENCORE OPERATING COMPANY Phone: (785) 737-3242

Proposed Plugging Method: Ordered out 375 sxs 60/40 pozmix - 10% gel - 500# hulls.
DV at 1575' w/750 sxs. PBTD 3884'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/22/2004 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2000'.
Allied pumped 165 sxs 60/40 pozmix - 10% gel with 500# hulls - circulated cement.
PTOH. Allied squeezed with 110 sxs cement.
Max. P.S.I. 900#. S.I.P. 900#.
Hooked up to backside - instant 500#. (DV at 1575' w/750 sxs)

Perfs:

Top	Bot	Thru	Comments
3738	3766		

RECEIVED
NOV 24 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

103-

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 11-29-04

INV. NO. 2005060854

NOV 22 2004

STANOLIND OIL & GAS

#2

IRVIN

6-14-19W
NE SW NE

Contr. HERNDON DRILLING

ELLIS

County

E. 2273 RBComm.

Comp. 11-27-53

IP

135 BOPD

PHY POT

Tops	Depth	Datum
HEEB	3510	-1237
LANS	3555	-1282
B/KC	3804	-1531
CONG	3847	-1574
ARB	3886	-1613
TD	3906	-1633

Casing

8" 179

6" 3888

DST 3896-3906/1 HR, 80' OIL

60' H MCO, BHP 1135#

CO 3906: 2 BOPH: SANDFRAC:

8 BOPH, TR WTR

IRVIN POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

4706