

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19137-00-00
Spot: SESE Sec/Twnshp/Rge: 32-13S-15W
660 feet from S Section Line, 660 feet from E Section Line
Lease Name: BAXTER A Well #: O-12
County: RUSSELL Total Vertical Depth: 3105 feet

Operator License No.: 31428
Op Name: CRAWFORD, JEFF DBA LONESTAR OIL
Address: PO BOX 417
VICTORIA, KS 67671

PROD Size: 5.5 feet: 3059
SURF Size: 8.625 feet: 235

100 91

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/03/2004 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JEFF CRAWFORD Company: CRAWFORD, JEFF DBA LONESTAR Phone: (785) 735-2725

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/03/2004 10:30 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Tied onto backside and pumped 35 sxs 60/40 pozmix - 10% gel cement - cement coming up in cellar.
Tied onto 5 1/2" and pumped 205 sxs cement with 500# hulls.
Max. P.S.I. 500#. S.I.P. 400#.

Perfs:

RECEIVED
NOV 29 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

Case Morris

(TECHNICIAN)

INVOICED

DATE 11-29-04
INV. NO. 2005060851

Form CP-2/3

NOV 24 2004

HOME-STAKE PROD

#0-12 BAXTER

32-13-15W

SE SE

Contr. A L JACKSON

RUSSELL

County

E 1906 RB Comm

Comp. 11-3-61

IP 25 BOPD/LANS

Tops	Depth	Datum
TOP	2786	-880
HEFB	3004	-1098
-TOR	3025	-1119
LANS	3054	-1148
TD	3105	-1199

Casing

8" 235

5" 3059

DD 3109

GORHAM POOL

DICK GREEN, GEOL.

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

J-210

FR 3-118

FR & COMP.

MAP NO.

SEC 32-13S-15W

STATE Kans. COUNTY

Russell

LOC C SE SE

OPER Home Stake Prod. Co.

FT/FR LINE

WELL 0-12 FARM Harry Baxter

FT/FR LINE

POOL Gorham

ELEV 1901

GR 1903

DC 1906

KB

CONT. A. L. Jackson Tools

GEOL.

CO.

INT

FR 3-16-64

SPUD 9/30/61

COMP.

3-24-64

TD 3111

FM.

PRTD

Completion Record

PRODUCING FM.

FROM

TO

PERF W/POLES

TREATMENT

Lans

3059-3111

OH

none

Oil Well producing on Water Flood

8-5/8" @ 235 w/235

5 1/2" @ 3059 w/200

Data Inc.

KB Spl Tops:

Anh 943 + 963 no other tops available

RTD 3062 -1156

RTD 3062, 5 1/2" @ 3059 w/200 sx., RUCT, DD 3111 TD

Oil Well producing on Water Flood (Lans 3059-3111) COMPLETE

FIRST REPORTED & COMPLETED 3-16-64

(10/19/61)

INDEX