

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20232-00-00
Spot: NESESW Sec/Twnshp/Rge: 25-12S-20W
990 feet from S Section Line, 2970 feet from E Section Line
Lease Name: KOHL Well #: 2
County: ELLIS Total Vertical Depth: 3985 feet

Operator License No.: 8315
Op Name: KISKA OIL COMPANY
Address: 507 S. MAIN, #501
TULSA, OK 74103

PROD Size: 5.5 feet: 1546 w/525 sxs cmt
SURF Size: 8.625 feet: 214 w/140 sxs cmt

#12951

Well Type: SWD UIC Docket No: D14319.0 Date/Time to Plug: 10/01/2004 2:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: DON BRADSHAW Company: KISKA OIL COMPAY Phone: (918) 584-4251

Proposed Plugging Method: Ordered 125 sxs 60/40 pozmix - 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/01/2004 3:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Tied to 5 1/2" casing and squeezed 63 sxs cement and 150# hulls.
Max. P.S.I. 200#. S.I.P. 200#.
Visual inspection of 8 5/8" x 5 1/2" annulus. Full of cement.
Total 63 sxs Swift Multi-Density cement and 150# hulls.
Dakota 438' - 734'. Cedar Hills 926' - 1256'. Anhy. 1519' - 1563'. Salt 1900' - 2080'.

Perfs:

RECEIVED
NOV 24 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC. STEWART TANK-WATER.

Plugged through: CSG

District: 04

Signed Roger Moses
(TECHNICIAN)

INVOICED


DATE 11.29.04
INV. NO. 2005060857

Form CP-2/3

NOV 22 2004

25-12-20W
NE SE SW

O. B. MOBLEY, JR. ETAL #2 KOHL
 Contr. HELLAR DRLG Cty. ELLIS
 Geol. Pool WEISNER POOL
 E. 2163 KB Cm. 3/31/68 Cp. 5/30/68 IP SWDW - RATE OK
 CEDAR HILL
 1100-1250



LOG Tops	Depth	Datum
ANHY	1519	+ 644
TOP	3186	-1013
HEEB	3440	-1277
TOR	3462	-1299
LANS	3482	-1319
BKC	3731	-1568
ARB	3874	-1711
LID	3983	-1820
RTD	3985	-1822

Csg. 8" 214/140 SX, 5" 1546.
 DST 3497-3520/90", 20' MD, BHP
 248-89#/30", FP 31-31#
 DST 3520-48/70", 250' SLI O&GCMW
 BHP 1270-1239#/30", FP 52-116#
 DST 3616-34/49", 20' SLI OCM, BHP
 36-68#/30", FP 36-36#
 DST 3666-95/90", 75' MW/SP OIL,
 BHP 1182-1130/30", FP 58-58#
 DST 3875-3880/92", 5' MW/SP OIL,
 FP 31-26#/30", FP 15-15#
 DST 3880-3890/94", 60' GIP, 5' O
 10' HOCM, 60' OCM, BHP 819-
 673#/30", FP 52-58#
 DST 3880-95/3', 90' GIP, 25' FO,
 45' SOCM, BHP 886-761#, 26-31#
 DST 3813-33 (SP) 70", 10' M, BHP 15-
 15#/30", FP 10-10#
 CO PF 1100-1250, SWDW - RATE OK

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS