

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 151-22,159-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date \_\_\_\_\_.

Well Operator: KENNETH S. WHITE KCC License #: 30128 6/05  
(Owner / Company Name) (Operator's)

Address: 2400 N. Woodlawn, Suite 115 City: Wichita

State: Kansas Zip Code: 67220 Contact Phone: ( 316 ) 682 - 6300

Lease: Green Well #: 1 Sec. 33 Twp. 26 S. R. 12  East  West

E/2 - NE - NW - \_\_\_\_\_ Spot Location / QQQQ County: Pratt

660 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

2310 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: None Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 10-3/4" Set at: 316 Cemented with: 250 Sacks

Production Casing Size: 5-1/2" Set at: 4429 Cemented with: 135 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perf @ 4332-35, CIBP @ 4330, Perf @ 4317-20, CIBP @ 4302, Perf @ 4283-88, CIBP @ 4280, Perf @ 4222-26

Elevation: 1907 ( G.L. /  K.B.) T.D.: 4429 PBTD: 4280 Anhydrite Depth: 1260' - 1920'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Fill with sand to 4150' and dump 5 sx cement, shoot casing for recovery, pull casing and plug @ 1920' with 50 sx cement, 75 sx cement @ 330', 25 sx @ 40', 60/40 PozMix, 6% gel

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? Filed with ACO-1

RECEIVED  
NOV 29 2004  
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: \_\_\_\_\_

Herb Durant Phone: ( 620 ) 886 - 5463

Address: P.O. Box 251 City / State: Medicine Lodge, KS 67104

Plugging Contractor: Mike's Testing & Salvage, Inc. KCC License #: 31529 9/05  
(Company Name) (Contractor's)

Address: P.O. Box 467, Chase, KS 67524 Phone: ( 620 ) 938 - 2943

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11/24/04 Authorized Operator / Agent: Kenneth S. White  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

White, Kenneth S.  
2400 N. Woodlawn, Suite 115  
Wichita, KS 67220

December 09, 2004

Re: GREEN #1  
API 15-151-22159-00-00  
E2NENW 33-26S-12W, 660 FNL 2310 FWL  
PRATT COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,  


David P. Williams  
Production Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888