

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-19123-00-01
API NUMBER completed on 8-18-50

LEASE NAME Kohman

WELL NUMBER 2

4290' Ft. from S Section Line

990' Ft. from E Section Line

SEC. 33 TWP. 5S RGE. 20 (EXX(W))

COUNTY Phillips

Date Well Completed 8-18-50

Plugging Commenced 10-4-85

Plugging Completed 10-4-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Cities Service Oil & Gas Corporation

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112

PHONE# (405) 949-4400 OPERATORS LICENSE NO. 5447

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District Office #6

Is ACO-1 filed? completed on 8-18-50 If not, is well log attached? yes

Disposal 8-18-50
~~XXXXXX~~ Formation Granite Wash Depth to Top OH 3668 Bottom 3741' T.O. 3741'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Granite Wash	(Inj.)	3668	3741	10-3/4"	153'	0'
				7"	3660'	0'
				5-1/2"	157'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Spotted 60 sx cmt & 27 sx gel 3450-3668'. Perf anhydrite at 1670'. Pumped 40 sx cmt followed by 8 sx gel. Perf. Dakota base at 1070. Pumped 40 sx cmt followed by 5 sx. gel. Spotted 200 sx cmt. 200' - surface. Pumped 50 sx down 10-3/4" X 7" csg annulus. State Witness: Mr. Dale Balthazor.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____

Address Box 47, Oberlin, Kansas 67749

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Del G. Oliver, Engineering Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Del G. Oliver
3545 NW 58th Street

(Address) Oklahoma City, OK 73112

SUBSCRIBED AND SWORN TO before me this 25 day of November, 1985

Jessie Jo Howell
Notary Public

My Commission Expires: 4-24-89

STATE CORPORATION COMMISSION

NOV 27 1985
11-27-85
CONSERVATION DIVISION