

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-137-20,296 -20-00

LEASE NAME Glenn

WELL NUMBER 1

1650 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 7 TWP. 5 RGE. 21SW(E) or (W)

COUNTY Ellis

Date Well Completed 9-7-83

Plugging Commenced 12-3-91

Plugging Completed 12-3-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR R.P. Nixon Operations, Inc.

ADDRESS 207 W. 12th Hays, KS 67601

PHONE#(913) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-3-91 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? Lansing 3238' BKC 3424'

Producing Formation L/KC, Reagan Sd Depth to Top Reagan 3480' Bottom 3484' T.D. 3484'

Show depth and thickness of all water, oil and gas formations.

12-12-91

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

| Formation | Content | From | To | Size | Put in | Pulled |
|-----------|---------|---------|-------|--------|--------|--------|
| | | Surface | 209' | 8 5/8" | 209' | none |
| | | Surface | 3481' | 4 1/2" | 3481' | none |
| | | | | | | |
| | | | | | | |

DEC 12 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Perforated 4 1/2" casing at 1660' & 1000' with one shot each depth. Pumped down 4 1/2" with 320 sx 60/40 pozmix and 500# hulls. Shut in pressure 500#. Pumped down 4 1/2" annular space with 100 sx of same type cement. Shut in pressure on backside was 300#. KCC man Carl Goodrow on location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jay-Lan Corp. License No. 5128

Address 207 West 12th Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Dan A. Nixon (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 207 W. 12th Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 10th day of December, 19 91



Roxie VonIntel
Notary Public

My Commission Expires: 5-21-93