

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market - Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-067-20646-0000

LEASE NAME TUTTLE

WELL NUMBER 3-9

3450' FSL Ft. from S Section Line

3500' FEL Ft. from E Section Line

SEC. 9 TWP. 30S RGE. 37W (E) or (W)

COUNTY GRANT

Date Well Completed 3/07/87

Plugging Commenced 11/09/04

Plugging Completed 11/11/04

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # (72) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/08/04 (date)

by DAVID WILLIAMS (KCC District Agent's Name)

is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation CHASE Depth to Top 3107' KB Bottom 2859' T.D. 2950'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE	GAS	2428'	2740'	8 5/8"	620'	0
				5 1/2"	2950'	525'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set

11/09/04 KCC notified. Set CIBP @ 2370'. Spot 20' cement. 11/11/04 KCC notified Cntr to 5 1/2" csg. load hole w/60 bbl mud. Cut csg at 525'. Circ w/40 bbl mud + 50 sx cmt plug from 525' to 375', displ cmt w/10 bbl mud. Load hole w/5 ppg mud to 40', pmped 10 sx cmt 40' to 0'. Cut 8 5/8" csg 3' bql, weld trash cover ID plate, RDMO

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.


LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039

SUBSCRIBED AND SWORN TO before me this 3rd day of December, 20 04

My Commission Expires: 3/23/06 Notary Public



RECEIVED  
DEC 06 2004  
KCC WICHITA

USE ONLY ONE SIDE OF EACH FORM

Form CP-4  
Revised 05-88