

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form GP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Webco Oil Company
Address: 2136 NE 90th Ave., Hoisington, KS 67544
Phone: (620) 587-3539 Operator License #: 6357
Type of Well: SWD Docket #: D-20985
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: November 23rd, 2004 (Date)
by: Herb Deines / Case Morris (on location) (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 3385' Bottom: 3385' T.D. 3547'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 009-22580 - 00 - 00
Lease Name: Prosser SWD
Well Number: #3
Spot Location (QQQQ): SE - SE - SE -
330' Feet from North / South Section Line
330' Feet from East / West Section Line
Sec. 33 Twp. 16 S. R. 12 East West
County: Barton
Date Well Completed: 11/13/1981
Plugging Commenced: 11/24/04
Plugging Completed: 12/02/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	382'	8-5/8"	382'	0'
	Production	0'	3376'	4-1/2"	3376'	512.95'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Backhoe operator took out dike, leveled location, dug cellar and pit. M.I.R.U. Rigged over for tubing. Built floor - picked tubing out of slips. Tubing hung up. Left tension pulled into it for the night. Trip in hole w/tubing swab to 3000'. M.I.R.U. L-K Wireline. Tried to trip in hole with stretch tool - wouldn't go. Trip in hole and tried to cut @ 2500' - wouldn't come. Trip in hole and cut @ 2000'. Trip out of hole w/59 joints-2-3/8" fiberglass tubing. Broke head out. Rigged tongs over for casing. Hooked up knife and rigged up casing jacks. Pulled casing out of slips-only 2" of stretch. Called state-changed plugging orders. Copeland pumped 130 sx w/200# hulls w/12 bbls displacement. Trip in hole w/knife and cut casing. Pulled 2 jts.-pumped 30 bbls slurry. Pulled 10 jts-pumped rest of cement-well never circulated. R.D.M.O.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc License #: 6901

Address: P.O. Box 231, Claflin, Kansas 67525

Name of Party Responsible for Plugging Fees: Webco Oil Company

State of Kansas County, Barton, ss.

Edward S. Nemnich

(Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature)
Edward S. Nemnich
KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 4/13/06

P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED and SWORN TO before me this 2nd day of December, 20 04

Karen J. Mitchell
Notary Public

My Commission Expires: 4/13/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
DEC 08 2004
KCC WICHITA

[Handwritten mark]