

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Dart Cherokee Basin Operating Co. LLC

Address: 3541 County Road 5400, Independence, Ks. 67301

Phone: (620) 331-7870 Operator License #: 33074

Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 9/16/04 (Date)

by: Alan Dunning (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

N/A Depth to Top: _____ Bottom: _____ T.D. 1450

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-125-19833-00-00

Lease Name: Lucas

Well Number: #1 GPS

Spot Location (QQQQ): _____ - SW - SE - NE

3250 Feet from ☐ North / ☒ South Section Line

660 Feet from ☒ East / ☐ West Section Line

Sec. 2 Twp. 35 S. R. 14 ☒ East ☐ West

County: Montgomery

Date Well Completed: N/A

Plugging Commenced: 9/16/04

Plugging Completed: 9/16/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	200'	7"	200'	0
		0	1450'	4 1/2"	1450'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated well at 900, 600, and 300 feet. Ran tubing to 1445 feet and filled well from bottom to surface with cement.

Pulled tubing out of well and topped off with cement. A total of 111 sacks of portland cement were used to plug the well. Cut well off below plow depth and restored location.

Name of Plugging Contractor: W & W Production Company License #: 5491


Address: 1150 Hwy 39, Chanute, Ks. 66720

Name of Party Responsible for Plugging Fees: Dart Cherokee Basin Operating Co. LLC. CHANUTE, KS

State of Kansas County, Montgomery, ss.

Tony Williams (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Tony Williams

(Address) 3541 County Road 5400, Independence, Ks. 67301

SUBSCRIBED and SWORN TO before me this 27th day of September, 20 04

Lisa Shartzter My Commission Expires: 5-26-06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202