

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Pratt Well Service, Inc.
Address: P.O. Box 847, Pratt, KS 67124
Phone: (620) 672-6520 x 13 Operator License #: 5893
Type of Well: gas Docket #: _____
(Oil, Gas, G&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: Nov. 10, 2004 (Date)
by: Steve Durrant per faxed instructions (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
4562'-4572' Depth to Top: _____ Bottom: _____ T.D. _____
4537'-4541' Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-151-21145-00-00
Lease Name: Calbeck
Well Number: 1
Spot Location (QQQQ): C - E/2 - NE - SE
330' Feet from North / South Section Line
1980' Feet from East / West Section Line
Sec. 9 Twp. 28S S. R. 15 East West
County: Pratt
Date Well Completed: 06/82
Plugging Commenced: Nov. 10, 2004
Plugging Completed: Nov. 11, 2004

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	@416'	
				4 1/2"	@4798'	37 Jts - 2190'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

To location, unpacked 4 1/2" well head and pulled slips. Loggers set b. plug @ 4480' w/ 2 sks cement on top. Water truck ran 30 BBLs. Loggers shot casing @ 2480', but it didn't cut.

Shot again @ 2190' and pulled 3 jts-4 1/2". Pulled 34 jts-3 1/2" and rigged down.

1st plug @ 975' w/ 50 sks 60/40 poz - 2nd plug @ 420' w/ 50 sks 60/40 poz - 3rd plug @ 40' w/ 10 sks 60/40 poz

Name of Plugging Contractor: Pratt Well Service, Inc. License #: 5893
Address: P.O. Box 847, Pratt, KS 67124
Name of Party Responsible for Plugging Fees: Pratt Well Service, Inc.
State of Kansas County, Pratt, ss.
Amy Robertson, Production Clerk

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Amy Robertson, Production Clerk

(Address) P.O. Box 847, Pratt, KS 67124

KEVIN C. GATES
Notary Public - State of Kansas
My Appt. Expires 3/13/08

Subscribed and SWORN TO before me this 22 day of November, 2004
Kevin C. Gates My Commission Expires: 3/13/08
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
NOV 29 2004
KCC WICHITA

KCC
BEM
12/10/04
RBDMS

KCC
BEM
12/9/04
Per Oper

[Handwritten signature]