

12-3

112
R

4- 031619

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-137-20,310 -00-00

NE NE SW /4 SEC. 07, 05 S, 21 W
2310 feet from S section line
2970 feet from E section line

Operator license# 5252 Lease Glenn well # 2

Operator: R.P. Nixon Operations Inc. County Norton 113.36

Address: 207 West 12th Street Well total depth 3488 feet PBSD 3434
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 213 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Jay-Lan Corporation License# 5128

Address: 207 West 12th Street, Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 3 Month: December Year: 91

Plugging proposal received from: Paul Nixon

Company: R.P. Nixon Operations Inc. Phone:

Were: Order 450 sx. 65/35 pozmix - 10% gel. - 500# hulls.
B.J. Services. Tracy Water Trucks. Shots @ 1660' and 1000'.
Casing open across perms. with wireline.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All X], Part], None]

Completed: Hour: 4:00 P.M., Day: 3, Month: December, Year: 91

Actual plugging report: 8 5/8" @ 213' w/135 sks. 4 1/2" @ 3487' w/125
sks. Top perf. @ 3386'. Squeezed 4 1/2 w/400 sx. cement blend w/500
hulls mixed in. Squeezed 8 5/8" w/150 sx. cwc. from 1000'.

Max. pressure on 4 1/2" - 700 P.S.I. Shut in @ 300 P.S.I.

Max. pressure on backside - 400 P.S.I. Shut in @ 400 P.S.I. RECEIVED
STATE CORPORATION COMMISSION

Total sacks 400 cement.

DEC 16 1991

Remarks: No stretch on 4 1/2. 12-16-91
CONSERVATION DIVISION

INVOICED

did not observe the plugging.

Carl Goodrow

DATE 1-7-92

(agent)

INV. NO. 34221

Form CP-2/3