

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21358-00-01
Spot: NWESW Sec/Twnshp/Rge: 13-28S-19W
2230 feet from S Section Line, 3640 feet from E Section Line
Lease Name: PAULY Well #: 1
County: KIOWA Total Vertical Depth: 4910 feet

Operator License No.: 5118
Op Name: TGT PETROLEUM CORPORATION
Address: 7570 W 21ST ST N, STE1010D PO BOX
WICHITA, KS 67275

CIBP Size: feet: 4620
PROD Size: 5.5 feet: 4898 WITH 255 SX CMT
SURF Size: 8.625 feet: 498 WITH 275 SX CMT **\$159⁵⁸**

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/08/2004 2:45 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JERRY SULLIVAN Company: TGT PETROLEUM Phone: (316) 773-2266

Proposed Plugging Method: SAND BACK TO 4400' & 5 SX CMT. PLUG AT 1250' WITH 12 SX GEL & 50 SX CMT. PLUG AT 510' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: PARTIAL
Date/Time Plugging Completed: 11/09/2004 12:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4867'. SANDED BACK TO 3800' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 1250' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 510' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4836	4840		
4490	4494		

RECEIVED
DEC 06 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2520' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
DATE 12-7-04
TOL. NO. 2005060899

Form CR-275