

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21843-00-00
Spot: E2SWNW Sec/Twnshp/Rge: 19-16S-29W
3429 feet from S Section Line, 4475 feet from E Section Line
Lease Name: MAGIE Well #: 1
County: LANE Total Vertical Depth: 4550 feet

Operator License No.: 3062
Op Name: QUESTA ENERGY CORPORATION
Address: PO BOX 19297 3601 S. GEORGIA
AMARILLO, TX 79114

SURF Size: 8.625 feet: 380

\$147⁸⁸

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/16/2004 7:45 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ROB MCGARRAUGH Company: _____ Phone: _____

Proposed Plugging Method: 1ST PLUG AT 2240' WITH 50 SX CMT. 2ND PLUG AT 1300' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 40 SX CMT. 4TH PLUG AT 400' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: NONE
Date/Time Plugging Completed: 11/16/2004 11:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

Perfs:

1ST PLUG AT 2240' WITH 50 SX CMT. 2ND PLUG AT 1300' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 40 SX CMT. 4TH PLUG AT 400' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED
DEC 06 2004
KCC WICHITA


Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
DEC - 1 2004
KCC Dodge City

Signed



(TECHNICIAN)

INVOICE

DATE 12.7.04
2005060896

Form SP-2/3