

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-20929-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 5-28S-15W  
4950 feet from N Section Line, 330 feet from W Section Line  
Lease Name: HEALY FAMILY FARMS Well #: 1  
County: PRATT Total Vertical Depth: 4685 feet

Operator License No.: 5893  
Op Name: PRATT WELL SERVICE, INC.  
Address: PO BOX 847  
PRATT, KS 67124

CIBP Size: feet: 4500 WITH 2 SX CMT  
PROD Size: 4.5 feet: 4684 WITH 125 SX CMT  
SURF Size: 8.62 feet: 469 WITH 350 SX CMT

*26*  
*\$152*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/10/2004 8:45 AM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: GEARLD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: SET CIBP @ 4500' WITH 2 SX CMT. PLUG AT 950' WITH 50 SX CMT. PLUG AT 480' WITH 50 SX CMT. PLUG AT 40'W TIH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/10/2004 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4500' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 950' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 480' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4576	4585		

RECEIVED  
DEC 06 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICE. RECOVERED 2910' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

*Stephen J. Pfeifer*  
(TECHNICIAN)

INVOICED  
DATE 12.7.04  
INV. NO. 2005060895

Form CP 2/3