

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21145-00-00
Spot: E2NESE Sec/Twnshp/Rge: 9-28S-15W
1980 feet from S Section Line, 330 feet from E Section Line
Lease Name: CALBECK Well #: 1
County: PRATT Total Vertical Depth: 4800 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

CIBP Size: feet: 4480 WITH 2 SX CMT
PROD Size: 4.5 feet: 4798 WITH 200 SX CMT
SURF Size: 8.625 feet: 416 WITH 275 SX CMT

#156⁰⁰

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/12/2004 8:45 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GERALD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: SET CIBP @ 4480' & 2 SX CMT. PLUG AT 975' WITH 50 SX CMT. PLUG AT 420' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/12/2004 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4480' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 975' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 420' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4562	4572		
4537	4541		

RECEIVED
DEC 06 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2196' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
NOV 23 2004
KCC Dodge City

Signed Stephen J. Pfeifer
(TECHNICIAN)

INVOICE
DATE 12-7-04
INV. NO. 2005060895

Form CP-2/5