

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20804-00-01
Spot: NESWSW Sec/Twnshp/Rge: 31-22S-11W
1200 feet from S Section Line, 850 feet from W Section Line
Lease Name: ALLEN Well #: 8
County: STAFFORD Total Vertical Depth: 3590 feet

Operator License No.: 32432
Op Name: LA VETA OIL & GAS, LLC
Address: PO BOX 780
MIDDLEBURG, VA 20118

PROD Size: 5.5 feet: 3590
SURF Size: 8.625 feet: 560

\$ 116⁶⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/14/2004 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 2729' & 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/14/2004 12:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 2729' & 5 SX CMT. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3422	3427		
3402	3405		
3324	3328		
3297	3299		
3263	3268		
2778	2838		

RECEIVED
DEC 06 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID. RECOVERED 1640' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
NOV 24 2004
KCC Dodge City

Signed

Richard W. Lacey

(TECHNICIAN)

INVOICE

DATE

12-7-04

JVV NO

2005060893

[Signature]