

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20948-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 27-21S-12W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: SHUMWAY Well #: 2
County: STAFFORD Total Vertical Depth: 3617 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B 7 SW 26TH AVENUE
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 3615 WITH 125 SX CMT
SURF Size: 8.625 feet: 310 WITH 250 SX CMT

#11755

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/19/2004 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3250' WITH 5 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/19/2004 2:35 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3250' & 5 SX CMT WITH BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT WITH 100# HULLS MIXED IN. 2ND PLUG AT 330' WITH 50 SX CMT WITH 100# HULLS MIXED IN. 3RD PLUG AT 40' WITH 20 SX CMT. GOOD CIRCULATION THROUGHOUT JOB.

Perfs:


Top	Bot	Thru	Comments
3336	3342		

RECEIVED
DEC 06 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2428' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICE

DATE _____

QTY. _____

Form CP-2