

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-20796-00-01
Spot: NENWNW Sec/Twnshp/Rge: 3-22S-10E
292 feet from N Section Line, 824 feet from W Section Line
Lease Name: JACKSON-PIXLEE Well #: 9
County: GREENWOOD Total Vertical Depth: 2260 feet

Operator License No.: 5697
Op Name: JACKSON BROS., L.L.C.
Address: 116 EAST THIRD ST.
EUREKA, KS 67045

PROD Size: 4.5 feet: 2260
SURF Size: 8.625 feet: 60

73⁴⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/05/2004 8:00 AM
Plug Co. License No.: 5684 Plug Co. Name: SAGE, LARRY GEORGE
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' cement plug @ 2200' 50' cement plug @ 1000' 250' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: PARTIAL
Date/Time Plugging Completed: 11/15/2004 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

washed down & drilled to 2005', spotted 25 sxs cement @ 2000', pulled out tubing, shot casing @ 846' pulled casing out, ran tubing to 846', pumped 25 sxs cement, pulled tubing to 275', pumped 110 sxs cement to surface, pulled tubing out. gel spacers between plugs.

RECEIVED
KCC DISTRICT #3

NOV 29 2004 *mf*

CHANUTE, KS

RECEIVED
DEC 06 2004
KCC WICHITA

Remarks: OWWO REENTRY

Plugged through: TBG

District: 03

Signed Mike Heffern
(TECHNICIAN)

INVOICED

DATE 12-7-04
INV NO 2005060891