

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-23144-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 4-21S-11W  
880 feet from N Section Line, 2070 feet from E Section Line  
Lease Name: RUGAN F Well #: 2-4  
County: STAFFORD Total Vertical Depth: 3500 feet

Operator License No.: 5056  
Op Name: HOLL, F.G., COMPANY L.L.C.  
Address: 9431 E CENTRAL, SUITE 100  
WICHITA, KS 67206

PROD Size: 5.5 feet: 3498 WITH 175 SX CMT  
SURF Size: 8.625 feet: 267 WITH 225 SX CMT

*\$113<sup>75</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/17/2004 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND OFF TO 3300 WITH 5 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT. USE 10 SX GEL FOR SPACER.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/17/2004 8:50 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SAND TO 3272' & 5 SX CMT WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 550' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3376	3383		
3365	3374		
3358	3364		
3348	3356		

RECEIVED  
DEC 06 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GE' BY ACID SERVICES. RECOVERED 1808' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
NOV 23 2004  
KCC Dodge City

Signed

*Richard W. Lacey*

(TECHNICIAN)

INVOICED

DATE 12-7-04

INV. NO. 2005060889

*[Signature]*  
FORM OP-2/3