

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-26842-00-00
Spot: SESENWSE Sec/Twnshp/Rge: 22-23S-14E
1400 feet from S Section Line, 1570 feet from E Section Line
Lease Name: HAAS Well #: 15
County: WOODSON Total Vertical Depth: 1695 feet

Operator License No.: 5935

SURF Size: 8.625 feet: 41

Op Name: HAAS, MARK L.

Address: PO BOX 23449
SHAWNEE MISSION, KS 66283

55⁰⁹

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/04/2004 1:00 PM

Plug Co. License No.: 30567

Plug Co. Name: RIG 6 DRILLING CO., INC.

Proposal Rcvd. from: GEO

Company: GEORGE SEIFERT

Phone: (026) 939-4330

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED 6 3/4" BORE TO 1695'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT TD, A 50' CEMENT PLUG AT 700' AND A CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

Witness Type: NONE

Date/Time Plugging Completed: 11/04/2004 5:00 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

DRILL PIPE WAS RAN INTO THE WELL TO 1695'. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE DRILL PIPE TO 1695'. THE PIPE WAS PULLED TO 700' AND 10 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE PIPE WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE DRILL PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED
KCC DISTRICT #3

NOV 24 2004 CPT

CHANUTE, KS

RECEIVED
DEC 06 2004
KCC WICHITA

Remarks:

Plugged through: DP

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

INVOICED

DATE

12-7-04

INV. NO.

2005060888