

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-031-20294-00-00
Spot: Sec/Twnshp/Rge: 14-23S-13E
890 feet from S Section Line, 900 feet from E Section Line
Lease Name: JOE BAHR Well #: 20
County: COFFEY Total Vertical Depth: 2180 feet

Operator License No.: 5935
Op Name: HAAS, MARK L.
Address: PO BOX 23449
SHAWNEE MISSION, KS 66283

PROD Size: 5.5 feet: 2180
SURF Size: 8.625 feet: 20

\$ 70⁸⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/18/2000 9:00 AM
Plug Co. License No.: 5684 Plug Co. Name: SAGE, LARRY GEORGE
Proposal Rcvd. from: GEORGE SAGE Company: SAGE, LARRY GEORGE Phone: (620) 437-6103

Proposed Plugging Method: THIS WELL CONSISTED OF 5 1/2" CASING TO 2180' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT TD, A 50' CEMENT PLUG AT THE MISSISSIPPIAN, A 50' CEMENT PLUG AT THE KANSAS CITY, AND A CONTINUOUS CEMENT PLUG FROM 200' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 11/22/2004 10:30 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

2" TUBING WAS RAN INTO THE 5 1/2" CASING TO 2180'. 20 SACKS OF CEMENT WERE PUMPED THROUGH THE 2" TUBING TO 2180'. THE 2" TUBING WAS PULLED TO 1750' AND 30 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE 2" TUBING WAS PULLED TO 800' AND 18 SACKS OF CEMENT WERE PUMPED. THE 2" PIPE WAS PULLED TO 200' AND CEMENT WAS PUMPED INTO THE 2" TUBING UNTIL CEMENT CIRCULATED FROM THE 5 1/2" CASING AT SURFCE. ON 11/22/2004, AFTER THE CEMENT WAS SET UP, THE CEMENT WAS TAGGED AND 30 MORE SACKS OF CEMENT WERE USED TO BRING THE CEMENT TO SURFACE. BEFORE CEMENT THE 5 1/2" CASING WAS PERFORATED AT 800' AND AT 200' TO ENSURE THAT CEMENT WAS AT THOSE DEPTHS INSIDE AND OUTSIDE THE 5 1/2" CASING. BEFORE CEMENTING THE WELL WAS GELLED FOR BRIDGING PURPOSES.

RECEIVED
KCC DISTRICT #3

NOV 24 2004 CPT

CHANUTE, KS

RECEIVED
DEC 06 2004
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

INVOICED
DATE 12-7-04
INV. NO. 2005060888