

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21156-00-00
Spot: SESENE Sec/Twnshp/Rge: 29-17S-27W
2310 feet from N Section Line, 330 feet from E Section Line
Lease Name: MCBEE ^{KCC} ^{12/21/04} ^{12/28/05} ^{er-4} Well #: 1
County: LANE Total Vertical Depth: 4675 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: PO BOX 70 234 W. 11TH, STE A
HAYS, KS 67601

PROD Size: 5.5 feet: 4673 WITH 365 SX CMT
SURF Size: 8.625 feet: 428 WITH 225 SX CMT

#151 94

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/04/2004 3:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DEAN IVES Company: DAMAR RESOURCES Phone: (785) 625-0020

Proposed Plugging Method: PUMP 75 SX CMT & 500# HULLS TO BOTTOM OR SET B.P. AT 3600'. PUMP 40SX CMT W/3% CC & 100# HULLS AT 2000'. CIRCULATE CMT FROM 1600' TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/04/2004 7:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PERFORATED @ 1250' CEMENTED & CIRCULATED TO SURFACE. PUMP 75 SX COMMON CMT WITH 3% CC WITH 400# HULLS THROUGH TUBING AT 4200'. PUMP 40 SX COMMON CMT WITH 3% CC & 125# HULLS AT 2000'. PULL TUBING TO 1600' & PUMP 150 SX CMT. CIRCULATE CMT TO SURFACE. PULL TUBING OUT OF HOLE. TOP OFF 5 1/2" CASING WITH 25 SX CMT. HOLE STAYED FULL. 8 5/8" X 5 1/2" ANNULUS WAS CEMENTED IN. NO CMT PUMPED DOWN BACKSIDE.

Perfs:


Top	Bot	Thru	Comments
4239	4584		

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 07 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Ken Jehlik
(TECHNICIAN)

INVOICED

DATE 12-7-04

INV. NO. 2005060885