

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-22572-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 7-22S-11W  
4290 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: HAMMEKE C Well #: 1  
County: STAFFORD Total Vertical Depth: 3690 feet

Operator License No.: 6030  
Op Name: AINSWORTH OPERATING CO.  
Address: P.O. BOX 2334  
EDWARDS, CO 81632

PROD Size: 4.5 feet: 3690 WITH 135 SX CMT  
SURF Size: 8.625 feet: 292 WITH 175 SX CMT

93  
\$119

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/17/2004 3:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3400' & 4 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 320' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/17/2004 4:08 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3616'. ANHYDRITE @ 541'. SANDED TO 3400' & 4 SX CMT WITH BAILER. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 600' WITH 10 SX GEL-100# HULLS - 50 SX CMT. 2ND PLUG AT 330' WITH 100# HULLS - 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3450	3454		

RECEIVED  
DEC 06 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2463' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey  
(TECHNICIAN)

INVOICED  
DATE 12-7-04  
INV. NO. 2005060878

Form 2/3