

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22449-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 29-6S-20W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease Name: WYRILL Well #: 1
County: ROOKS Total Vertical Depth: 3739 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

PROD Size: 4.5 feet: 3725
SURF Size: 8.625 feet: 256

B/21/52

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/23/2004 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KEN VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered 300 sxs cement and 500# hulls.
Emergency plug with rig over hole.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/23/2004 11:00 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

P.C. at 1886' w/350 sxs cement - no circulation.
Perfed at 1200' w/350 sxs cement - still did not circulate.
Perfed again above 1200' - squeezed with 600 sxs cement.
Squeezed at 3726' with unknown amount cement.
Ran tubing to 3660' - spotted 100 sxs cement and 500# hulls.
Pulled tubing to 1650' - circulated with 60 sxs cement.
Pulled all tubing and topped off with 20 sxs cement.
Tied to 8 5/8" x 4 1/2" annulus - squeezed 30 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Total of 210 sxs 60/40 pozmix - 10% gel and 500# hulls.

Perfs:

RECEIVED
DEC 08 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. RGN TANK-WATER.

Plugged through: TBG

District: 04

Signed

Roger A. Moses

(TECHNICIAN)


INVOICED

12-8-04

2005060904

DEC 03 2004

BLACK DIAMOND OIL, INC. 29-6-20W
 1105 E. 30TH, #A #1 WYR III SW NW NW
 HAYS, KS 67601
 CONTR EMPHASIS OIL OPERATIONS CTY ROCKS
 GEOL KENNETH VEHIGE FIELD TODD
 ELV 2263 KB SPD 5/11/84 CARD ISSUED 3/7/85 P 10 BO & 10 BWPD
 ARB OH 3725-3738.5



LOG	Tops	Depth Datum	
			API 15-163-22,449
ANH	1864+	399	8 5/8 " 256, 4 1/2 " 3725
TOP	3244-	981	NO CORES OR DSTS
HEEB	3451-	1188	MICT - CO, (ARB OH), SWB DWN, NS, NAT, DD 3738.5 TD, SWB
TOR	3476-	1213	DWN, ONFU 1300' FL (85% OIL), NAT, AC 500G (15% INS), SWB
LANS	3488-	1225	2 BO / EA 15" FOR 2 HRS, PF (LKC) 1 / 3638, 1 / 3650, SWB
BKC	3682-	1419	DRY, AC 750G (15% MCA), SWB .75 BF (5% OIL) / EA 30", PF
MARM LM	3704-	1441	(LKC) 3567-69, W / 4 SPF, SET RBP AT 3607, SWB 18 BWPH /
CONG	3719-	1456	60", NAT, SQZ'D ALL LKC PFS W/200SX, PF (LKC) 1 / 3546, 1 /
ARB	3721-	1458	3478, SET RBP AT 3558, SWB DWN, AC 750G (15% MCA), SWB
RTD	3729-	1466	11 BW / EA 15" FOR 1 HR, SQZ'D PFS (3478 & 3546) W/200SX,
DDTD	3738.5-	1476	PULLED RBP, POP, P 10 BO & 10 BWPD (GR 26")

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

03010000