

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20799-00-00
Spot: NWNENE Sec/Twnshp/Rge: 34-8S-18W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: HARRIS Well #: 3
County: ROOKS Total Vertical Depth: 3466 feet

Operator License No.: 31824
Op Name: BROWN, THOMAS M.
Address: 403 NW 3RD PO BOX 250
PLAINVILLE, KS 67663

PROD Size: 4.5 feet: 3455 w/150 sxs cmt
SURF Size: 8.625 feet: 170 w/170 sxs cmt

#112 65

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/30/2004 9:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: THOMAS BROWN Company: BROWN, THOMAS M. Phone: (785) 434-7141

Proposed Plugging Method: Ordered out 260 sxs 60/40 pozmix - 10% gel - 500# hulls.
Squeeze at 1000' w/150 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/30/2004 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 180 sxs 60/40 pozmix - 10% gel with 400# hulls.
Max. P.S.I. 1000#. S.I.P. 500#.
Hooked up to backside. Allied pumped 45 sxs cement with 100# hulls.
Max. P.S.I. 650#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3103	3376		

RECEIVED
DEC 02 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Richard Williams
(TECHNICIAN)

10

INVOICED
DATE 12.3.04
NO. 2005060874

DEC 01 2004

GENE BROWN CO. #3 HARRIS 34-8-18W
 1000 SW 2ND PLAINVILLE, KS. 67663 NW NE NE
 CONTR HELBERG OIL CO. CTY ROOKS
 GEOL ROY KRUEGER FIELD DOPITA WEST

E 2005 KB CM 5/20/78 CARD ISSUED 9/7/78 IP P 10 BOPD + 60 BOPD

+	+	+	+
+	+	+	+
+	+	+	+

API 15-163-20,799 TOR 3156-60 &
 LKC 3260-3376 OA
 COMMINGLED

SMP	TOPS	DEPTH	DATUM
ANH		1397	+ 608
TOP		2917	- 912
HEER		3128	-1123
TOR		3149	-1144
LANS		3170	-1165
BKC		3395	-1390
CONG		3424	-1419
ARR NONE			
RTD		3466	-1461

8-5/8" 170/130sx, 4 1/2" 3455/150sx
 NO DST'S
 MICT - PF (TOR) 3156-60, AC 1500, PF
 (LKC) 3260-62, 3272-75, AC 1500, PF
 (LKC) 3333-36, 3352-54 & 3374-76,
 AC 1500, REC LD & POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS