

DISTRICT CONSERVATION AGENT'S REPORT

15-147-19129-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 148-37

LOCATION SW NW NW

SEC. 23 TWP. 5 RGE. 20

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Graham

Operator Skelly Oil Co Address Hutchinson, Kans

Field Ray NE County Phillips

Total Depth 3524 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 220' circulated with cement - 5 1/2" at 3489'
squeezed with cement and circulated with cement to bottom cellar.
Hole filled with sand to 2000', cable tools lost in hole at
2000' - Run tubing to 2000', circulated hole with commercial mud,
Pumped hole full cement from 250' to 0'. Through 2" tubing.
Mudding and cementing by Halliburton co

District Conservation Agent

Date 4-4-52'

PLUGGING
FILE SEC. 23 T. 5 R. 20
BOOK PAGE 148 LINE 37

APR 10 1952
0410-1952