

15-147 - 00619-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API Number (7/29/44) (of this well). (This must be listed; if no API# was issued, please note drilling completion data.)

WELL OWNER/OPERATOR OXY USA INC. OPERATORS LICENSE NO. 5447

ADDRESS P. O. Box 26100 Oklahoma City, OK 73126-0100 PHONE # (405) 749-2000

LEASE/FARM Brown "B" WELL NO. 1 WELL LOCATION 2310' FSL COUNTY Phillips

SEC. 23 TWP. 5S RGE. 20 ~~(E)~~ or (W) Total Depth 3583' PLUG BACK TD 3500'

CHECK ONE:

OIL WELL X GAS WELL D & A SWD OR INJ WELL DOCKET NO.

SURFACE CASING SIZE 8-5/8" SET AT 160' CEMENTED WITH 185 SACKS

CASING SIZE 5-1/2" SET AT 3541' CEMENTED WITH 150 SACKS

PERFORATED AT 3246-3455' (9 - sets perforations)

CONDITION OF WELL: GOOD POOR CASING LEAK X JUNK IN HOLE X

PROPOSED METHOD OF PLUGGING Procedure is attached for K.C.C. approval.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN: 11/16/90

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq
AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mr. J. D. Hininger PHONE # (913) 674-2182
ADDRESS OXY USA INC., P.O. Box 38, Hill City, KS 67642

PLUGGING CONTRACTOR J.W. Gibson Well Service Co. LICENSE NO. 5866

ADDRESS 7400 E. Orchard Rd. #370, Englewood, CO PHONE # (303) 771-5222
Zip 80111-2531

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

STATE CORPORATION COMMISSION

SIGNED: Philip W. Pringle
(Operator or Agent)

OCT 16 1990

10-16-1990

Wichita, Kansas

DATE: 10-16-90

4

Geol. 63 10M 6-43

WELL RECORD

15-147-00619-00-00

Company CITY SERVICE OIL CO. Well No. 1 Farm Brown #2
 Location 390' South and 990' East of W/4 Corner Sec. 23 T. 5 R. 20W
 Elevation 2166 County Phillips State Kansas
 Initial Prod. Physical Potential: 210 oil, 0 water, 24 hours Contractor R. W. Rine Drilling Co.
 Acid None Drig. Comm. July 13, 1944
 T. D. 3583' Drig. Comp. July 29, 1944

CASING RECORD:

8-5/8" @ 160' cem. 125 sx bulk cem.
 and 2 sacks C. C.
 Recemented top of 8-5/8"
 with 60 sx cem. & 100#
 C. C.
 5-1/2" @ 3541' cem. 150 sx Halliburton
 bulk cem.

Set 60' of 4-1/2" liner at 3583'

FORMATION RECORD:

clay & sand	0-120
clay	160
shale, sand & shells	975
shale & sand	1615
shale & shells	1680
anhydrite	1710
shale & lime	1950
lime & shale	2080
shale	2230
lime & shale	2335
shale	2535
shale & shells	2855
shale	3050
lime & shale	3252
lime	3350
lime & shale	3525
cored dolomite & sand (rec. 2')	3532
lime	3542
3542 Rot. TD = 3542 SLM	
lime	3543
lime & red rock	3555
lime	3583 T. D.



MEMORANDUM
OCCIDENTAL OIL AND GAS

15-147-00619-00-00

Wichita, Kansas
October 16, 1990

TO: Mr. M. D. Harrison
FROM: Mr. Phil W. Pringle
SUBJECT: PLUG AND ABANDON..... BROWN "B" #1
2310' FSL-4290' FEL
SEC 23-5S-20W
PHILLIPS COUNTY, KANSAS

WELL DATA

8-5/8" casing @ 160' w/ 185 sx
5-1/2" casing @ 3541' w/ 150 sx
Perforations: 3246-3455' (9 sets)

- * 2-3/8" tubing stuck in hole due to a casing leak.

SHALLOW FORMATION DATA

Dakota 720-880'
Cheyenne 930-1170'
Anhydrite 1680-1710'

-
1. Prior to plugging, obtain approval of project from the KCC District Office #4, Hays, KS, (913)628-1200.
 2. Attempt to shoot off the 2-3/8" tubing at \pm 3000'.
 3. Perforate with 4 SPF at 1670' and 930'.
 4. Run 2-3/8" workstring to 2990' and spot 65/35 cement w/ total 6% gel to surface. Pressure up to attempt circulation. (Approx. 360 sx cement)
 5. If circulation is not established, tie onto the 8-5/8" casing and fill the annulus to surface with 100 sx same cement.
 6. Let cement set 48 hrs., check TOC and cap well.

PWP/cd

State of Kansas



15-147-00619-00-00

Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
JACK SHRIVER
JUDITH MCCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

October 17, 1990

OXY USA, Inc.
P.O. Box 26100
Oklahoma City, OK 73126-0100

Brown "B" #1
2310'FSL-4290'FEL 23-05-20W
Phillips County, KS

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams

David P. Williams
Production Supervisor

District: #4, 2301 E. 13th
Hays, KS 67601
(913) 628 - 1200