

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM

15-147-00624-00-00 (File One Copy)

3-15-99

API Number 15-147-97507 (of this well). (This must be listed; if no API# was issued, please note drilling completion data.)

WELL OWNER/OPERATOR OXY USA INC. OPERATORS LICENSE NO. 5447 ⁶⁻⁸²

ADDRESS 110 S. Main #800, Wichita, KS 67202 PHONE # (316) 265-5624
4950' FEL

LEASE/FARM Brown "B" WELL NO. 4 WELL LOCATION 1650' FSL COUNTYPhillips

SEC. 23 TWP. 5S RGE. 20 (E) or Total Depth 3605' PLUG BACK TD _____

CHECK ONE:

OIL WELL GAS WELL _____ D & A _____ SWD OR INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 187' CEMENTED WITH 250 SACKS

CASING SIZE 5-1/2" SET AT 3563' CEMENTED WITH 150 SACKS

PERFORATED AT 3283-3559.5 (6-sets)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Will plug according to KCC requirements.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN: 4-3-92

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

J.D. Hininger PHONE # (913) 434-7681

ADDRESS Drawer D, Plainville, Kansas, 67663

PLUGGING CONTRACTOR J.W. Gibson Well Service LICENSE NO. 5866 ⁸⁷²

ADDRESS 505 W. Commercial, Logan, KS, 67646 PHONE # (913) 689-7573

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Carla J. Davis
Carla J. Davis
(Operator or Agent)

DATE: 3-4-92

4

WELL RECORD 15-147-00624-00-00

Company Cities Service Oil Co. Well No. 4 Farm Brown "B"
 Location 990' South and 330' East of W/4 Corner Sec. 23 T. 5 R. 20W
 Elevation 2156 (2154 Gr.) County Phillips State Kansas
 Drlg. Comm. February 11, 1949 Contractor R. W. Rine Drilling Company
 Drlg. Comp. March 15, 1949 Acid See Below
 T. D. 3605' Initial Prod. Physical Potential: 207 oil, no water, 24 hrs. (4-20-49)
 P.B.T.D. 3491'

CASING RECORD:

8-5/8" @ 187' cem. 250 sx cement
 w/ 200# C. C.
 5-1/2" @ 3563' cem. 150 sx cement

FORMATION RECORD:

clay & sand	0-110
shale	187
sand & shale	1650
anhydrite	1690
shale & shells	2585
shale & lime	3185
lime & shale	3350
lime	3545
cored: shale (rec. 6")	3546
lime	3555
cored: lime	3560
3560 RTD = 3564 SLM	
dolomite	3605 T. D.

Corr. Top Lansing	3284' -1128
Corr. Top Arbuckle	3550' -1394
Penetration	55'
Total Depth	3605'

75' water in 5-3/4 hrs. at 3605.

Plugged back to 3555' w/ rock and cement.
 Drilled cement to 3560 SLM.

Perf. 54 shots 3550-59 1/2
 1/2 bailer muddy wtr. w/ rainbow oil
 in 40 mins.

3-21-49 Acidized 500 gals. 3550-59 1/2
 No production.

Set Lane-Wells plug at 3491 SLM.

Perf. 40 shots 3373-84 - G
 " 34 shots 3362-71 - F
 " 35 shots 3283-94 - A

Acidized 3362-84 w/ 2000 gals. 3-25-49
 Acidized 3283-94 w/ 1000 gals. 3-25-49

SYFO: 500' 1°
 1000' 1°
 1500' 0°
 2000' 0°
 2500' 1°
 3000' 1°

RECEIVED
 STATE CORPORATION COMMISSION

7-7/8" rotary hole. MAR - 6 1992

CONSERVATION DIVISION
 Wichita, Kansas

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

15-147-00624-00-00

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

March 9, 1992

OXY USA INC
110 S Main 800
Wichita KS 67202

Brown B 4
4950' FEL-1650' FSL
Sec. 23-05-20W
Phillips County

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #4 2301 E. 13th
Hays, KS 67601
(913) 628-1200

Conservation Division
William R. Bryson
Director

200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1236
Telephone (316) 263-3238