

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23019-00-00
Spot: N2SWSW Sec/Twnshp/Rge: 32-6S-21W
990 feet from S Section Line, 660 feet from W Section Line
Lease Name: MANNY COOKSEY Well #: 1
County: GRAHAM Total Vertical Depth: 3775 feet

Operator License No.: 33306
Op Name: BLAKE EXPLORATION, LLC
Address: 201 S. MAIN, PO BOX 150
BOGUE, KS 67625

SURF Size: 8.625 feet: 215

#122⁶⁹

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/06/2004 4:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: LARRY PICKNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE Witness Type: NONE
Date/Time Plugging Completed: 12/06/2004 5:15 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 1850' w/25 sxs.
2nd. Plug at 1120' w/100 sxs.
3rd. Plug at 65' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

RECEIVED
DEC 09 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Bruce Basye
(TECHNICIAN)

INVOICE

DATE

12-9-04

INV. NO.

2005060905

Form CP-2/3

DEC 08 2004