

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20732-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 3-10S-29W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: KRANNAWITTER A Well #: 1
County: SHERIDAN Total Vertical Depth: 4225 feet

Operator License No.: 31900
Op Name: NOR-WEST KANSAS OIL, L.L.C.
Address: RR 2, BOX 14
WAKEENEY, KS 67672

PROD Size: 4.5 feet: 4226 w/125 sxs cmt
SURF Size: 8.625 feet: 258 w/175 sxs cmt

A137³¹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/02/2004 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: PAT WANKER Company: NOR-WEST KANSAS OIL, LLC Phone: (785) 743-2769

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 300# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/02/2004 12:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

8 5/8" surface casing set at 258' w/175 sxs cement.
4 1/2" production casing set at 4226' w/125 sxs cement.
DV tool at 2460'. Information not available in regards to amount of cement used.
Cement did not circulate. Top of cement at 1230'.
PBTd at 4112'.
Perforations 4096' - 4099' and 3986' - 3989'.
Connected to 8 5/8" surface casing - pumped 15 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Ran tubing to 4100' - pumped 70 sxs cement with 150# hulls.
Pulled tubing 2640' - pumped 80 sxs cement. Cement to surface.
Pulled tubing to surface.
Connected to 4 1/2" production casing - pumped 20 sxs cement.
Max. P.S.I. 1000#. Blew hole in casing above braden head.
S.I.P. 0#.

RECEIVED
DEC 09 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY - TICKET #18504.

Plugged through: TBG

District: 04

10

Signed Darrel Dipman
(TECHNICIAN)


INVOICED

DATE 12.9.04
INV. NO. 2005060910

DEC 03 2004

INDEXED

ANGLE EXPLORATION
405 ALLEGHENY DRIVE
COLORADO SPRINGS, CO 80919
CONTR GALLOWAY DRILLING CO.
GEOLOGIST T. SKINNER
REPLACEMENT CARD
#1 'A' KRANNAWITTER
3-10-29W
SW SW NW
CTY SHERIDAN
FIELD WCC SO. CONF & EXT
(1/4 NE)
ELV 2842 KB SPD 2/22/84 CARD ISSUED 5/10/84 IP P 150 BOPD, NW
2837 GL
API 15-179-20,732 LKC 3986-4098 OA



SMP	Top	Depth/Bottom	
			8 5/8 " 258 / 175SX, 4 1/2 " 4226 / 125SX NO CORES
ANH		2439 + 403	DST (1) 3624-3921 (TOP) / 15-60-60-60, REC 600' WM, 1400' MW, SIP 1184-1164#, FP 121-365 / 447-856#
B/ANH		2470 + 372	DST (2) 3976-4001 (LKC) / 15-60-60-60, 480' GIP, REC 1920' FREE GSY OIL, SIP 1293-1244#, FP 162-335 / 426-856#
TOP		3698 - 856	DST (3) 3999-4043 (LKC) / 30-30-30-30 REC 30' M, W / FEW OIL SPKS, SIP 1224-1164#, FP 60-60 / 60-60#
HEEB		3918 - 1076	DST (4) 4053-4130 (LKC) / 15-60-60-60, REC 300' FREE OIL, 1200' M & WC GSY OIL, 120' W, SIP 1372-1342#, FP 152-406 / 426-667#
LANS		3956 - 1114	DST (5) 4137-62 (LKC) / 15-60-60-60, REC 270' OIL, SIP 254- 162#, FP 63-71 / 111-121#
RTD		4225 - 1383	MICT - CO, PF (LKC) 3986-89, W / 4 SPF, SWB DWN, GSO, PF (LKC) 4095-98, W / 4 SPF, SWB DWN, GSO, SET 2 3/8 " TBG AT 4150', POP, P 150 BOPD, NW (GR 30"), 4/15/84

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

INFO RELEASED: 5/23/85 - WAS OIL WELL - TIGHT HOLE