

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00524-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 31-5S-20W
4290 feet from S Section Line, 2310 feet from E Section Line
Lease Name: PINKERTON Well #: 8
County: PHILLIPS Total Vertical Depth: 3616 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PROD Size: 5.5 feet: 3609 w/100 sxs cmt
SURF Size: 8.625 feet: 159 w/125 sxs cmt

117⁵²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/03/2004 12:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: RICK HOCKMAN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered out 300 sxs Swift Multi-Density cement and 500# hulls.
Fluid level 1448'. No squeeze records. Ran tubing to plug.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/03/2004 3:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3606'. Swift pumped 100 sxs SMD cement with 300# hulls.
Pulled tubing to 1400'. Swift pumped 80 sxs SMD - cwc.
PTOH. Squeezed with 15 sxs cement.
Max. P.S.I. 400#. S.I.P. 350#.
Hooked up to backside and pumped 50 sxs cement.
Max. P.S.I. 50#. S.I.P. 25#.

Perfs:

Top	Bot	Thru	Comments
1150	1800		

RECEIVED
DEC 09 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

PD

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 12-9-04
INV. NO. 2005060909

DEC 07 2004