

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00910-00-00
Spot: NENWNE Sec/Twnshp/Rge: 31-5S-20W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease Name: PINKERTON Well #: 15
County: PHILLIPS Total Vertical Depth: 3641 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PROD Size: 5.5 feet: 3635 w/150 sxs cmt
SURF Size: 8.625 feet: 203 w/250 sxs cmt

#118 33

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/02/2004 12:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: RICK HOCKMAN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered out 300 sxs Swift Multi-Density cement and 500# hulls.
Dakota 825' - 1125'. Anhy 1790' - 1810'.
No squeeze records. Fluid level 1412'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/02/2004 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3638'. Swift pumped 100 sxs Swift Multi-Density cement with 300# hulls.
Pulled tubing to 1396'. Swift pumped 75 sxs SMD with 200# hulls - cwc.
PTOH. Squeezed with 20 sxs cement.
Max. P.S.I. 700#. S.I.P. 400#.
Hooked up to backside and pumped 80 sxs cement.
Max. P.S.I. 100#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
1150	1800		

RECEIVED
DEC 09 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

ND

INVOICED

DATE 12-9-04

INV. NO. 2005060909

DEC 07 2004

CITIES SERVICE OIL CO. #15

PINKERTON

A^b 31-5-20W
NE NW NE

Contr. _____ PHILLIPS _____ County

E 2230 Comm. _____ Comp. 8-26-49 IP 2756 BOFD

Tops	Depth	Datum
LANS	3396	-1166
REAG	3634	-1404
T.D.	3641	-1411

Casing

8" 203 PMP 294 BO/15 HRS
5" 3635 PMP 222 BO/11 HRS

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

WADCO