

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00465-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 23-5S-20W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: GRAHAM B Well #: 2
County: PHILLIPS Total Vertical Depth: 3567 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PROD Size: 5.5 feet: 3501 w/150 sxs cmt
SURF Size: 8.625 feet: 191 w/150 sxs cmt

#115⁹³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/06/2004 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: RICK HOCKMAN Company: MURFIN DRILLING CO., INC. Phone: (785) 567-8060

Proposed Plugging Method: Ordered out 300 sxs Swift Multi-Density cement and 500# hulls.
Squeezed 1005' -1190' w/250 sxs cement.
Fluid Level 715' - 3370'. PBTB 3370'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/06/2004 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3363'. Swift pumped 100 sxs SMD cement with 300# hulls.
Pulled tubing to 1000'. Swift pumped 85 sxs cement with 200# hulls - circulated cement.
PTOH. Swift squeezed with 10 sxs cement.
Max. P.S.I. 600#. S.I.P. 350#.
Hooked up to backside - pumped 35 sxs cement.
Max. P.S.I. 50#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3242	3333		

RECEIVED
DEC 09 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 12-9-04
INV. NO. 2005060909

Form CP-2/3

DEC 07 2004

Skelly Oil Co.

2 Graham

23-5-20W
SW SW NW


Contr. _____ Phillips _____ County

E 2134 Comm. 10-28-43 Comp. 11-21-43 IP Pot. 284 Bbl.

Tops	Depth	Datum
LANS	3231	
ARB	3500	
T.D.	3567	

Casing
8" 191
5" 3501

Sat 3599-3504; 400'
OIH/3 hr; Sat 3504-
09, 1200' OIH/12 hr.
Sat 3509-16; 2000'
OIH/60 hr; A/3000



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

WADICEN