

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-20603-00-00  
Spot: W2NWNWNW Sec/Twnshp/Rge: 1-5S-20W  
330 feet from N Section Line, 160 feet from W Section Line  
Lease Name: PATRICIA UNIT Well #: 1-1  
County: PHILLIPS Total Vertical Depth: 3495 feet

Operator License No.: 33335

SURF Size: 8.625 feet: 1449

Op Name: IA OPERATING, INC.

Address: 800 N TYLER ROAD #14  
WICHITA, KS 67212

# 113<sup>59</sup>

Well Type: DH

UIC Docket No:

Date/Time to Plug: 12/06/2004 8:45 PM

Plug Co. License No.: 30606

Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: BILL WYNN

Company: MURFIN DRILLING CO., INC.

Phone: (316) 267-3241

Proposed Plugging Method: Order 210 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES

Witness Type: NONE

Date/Time Plugging Completed: 12/06/2004 10:45 PM

KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

1st. Plug at 3371' w/25 sxs.  
2nd. Plug at 1500' w/50 sxs.  
3rd. Plug at 875' w/100 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

RECEIVED  
DEC 09 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

INVOICED

DATE 12-9-04

INV. NO. 2005060907

DEC 08 2004