

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-00521-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 26-17S-25W
990 feet from N Section Line, 330 feet from W Section Line
Lease Name: LLOYD SPRUILL Well #: 1
County: NESS Total Vertical Depth: 4520 feet

Operator License No.: 5363

PROD Size: 5.5 feet: 4519 WITH 200 SX CMT

Op Name: BEREXCO, INC.

SURF Size: 9.625 feet: 236 WITH 150 SX CMT

Address: PO BOX 20380
WICHITA, KS 67208

#146⁹⁰

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/06/2004 12:40 PM

Plug Co. License No.: 32970

Plug Co. Name: H-D OIL FIELD SERVICE, INC.

Proposal Rcvd. from: MARK LEIKER

Company: BEREXCO INC

Phone: (316) 772-8649

Proposed Plugging Method: SPOT 30 SX CMT & 200# HULLS. PUMP 40 SX COMMON CMT WITH 3% CC AT 1400'. PERFORATE AT 1100' & PUMP 80 SX OVER CASING & 100 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 12/06/2004 5:30 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

LOCSET PACKER STUCK IN HOLE @ 2585' & A MODEL R PACKER IN HOLE AT 2332'. WELL WAS SQUEEZED AT 1277' TO 1365' WITH 100 SX CMT. RAN TUBING TO 2318' & SPOT 30 SX CMT. PULL TUBING TO 1400' & SPOT 40 SX COMMON CMT WITH 3% CC. WAIT 1 1/2 HOURS. TIED ONTO CASING & PRESSURED TO 600# & HELD FOR 30 MINUTES. PERFORATED AT 1100'. PRESSURED TO 1800#. COULD NOT PUMP IN TO. RAN TUBING TO 1100' & PUMPED 90 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TUBING & TIED ON TO CASING. TOOK 5 SX CMT TO LOAD. COULD NOT PUMP IN TO. TIED ONTO BACKSIDE & PUMPED 100 SX CMT. MAXIMUM PRESSURE 300#. SHUT IN PRESSURE 150#.

Perfs:


Top	Bot	Thru	Comments
4456	4462		
4371	4378		
4354	4365		

RECEIVED
DEC 10 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Michael Maier
(TECHNICIAN)

INVOICE
DATE 12-10-04
INV. NO. 2005060916

Form OR-273