

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21760-00-00
Spot: SWNENWSW Sec/Twnshp/Rge: 21-16S-23W
2119 feet from S Section Line, 4404 feet from E Section Line
Lease Name: BUXTON Well #: 1
County: NESS Total Vertical Depth: 4509 feet

Operator License No.: 9615
Op Name: GERSTNER, JOE
Address: 302 E. SYCAMORE
NESS CITY, KS 67560

PROD Size: 4.5 feet: 4508 WITH 150 SX CMT
SURF Size: 8.625 feet: 291 WITH 210 SX CMT

#146 54

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/03/2004 8:40 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: PAT GERSTNER Company: JOE GERSTNER Phone: (785) 798-2893

Proposed Plugging Method: SAND TO 3800' WITH 4 SX CMT. PLUG AT 710' WITH 40 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/03/2004 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED TO 3800' WITH 5 SX CMT. SHOT CASING AT 1007'. DID NOT COME LOOSE. PUMPED 80 SX CMT. SHOT CASING OFF AT 680'. CAME LOOSE. PULLED ONE JOINT AT 650' & PUMPED 50 SX CMT. PULLED TO 320' & PUMPED 50 SX CMT. PULLED REMAINING CASING & TOPPED OFF WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4459	4461		

RECEIVED
DEC 10 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 680' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Michael J. Maier
(TECHNICIAN)

INVOICED
DATE 12-10-04
INV. NO. 2005060918