

11-14 4-041857

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-147-20,168-00-07

C N2 /4 SEC. 23, 05 S, 20 W  
3960 feet from S section line  
2640 feet from E section line

Operator license# 5447

Lease: Hansen C Well # 7

Operator: OXY USA, Inc.

County: Phillips 120.96

Address: P.O. Box 300  
Tulsa, Oklahoma 74102-0300

Well total depth 3722 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 218 feet  
w/ 47 sxs.cmt.

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Halliburton Cementing, Inc. License# \_\_\_\_\_

Address: Hays, Kansas 67601

Company to plug at: Hour: 2:00 P.M. Day: 14 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3722' w/ 35 sxs.  
PSTD 3500+.  
Perfs at 3262' - 3266' - 3280' - 3282' - 3312' - 3318' - 3332' - 3338' - 3357' -  
3359' - 3540' - 3544' - 3597' - 3605'.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [ ], Part [ X ], None [ ]

Completed: Hour: 4:30 P.M., Day: 14, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. RIH with Howco and perfed at 1723' and 1100'. RIH with 2 3/8" to 3500'. R.U. Howco and pumped 65 sxs MIDCON 2 with 2% C.C. and 200# hulls. POOH with 48 jts to 2000'. Pumped 65 sxs cement & 200# hulls. POOH with 48 jts. to 500'. Pumped 40 sxs cement and circulated to surface. POOH with rest of tubing. Pumped 30 sxs and S.I.P. 300#. Hooked onto backside and pumped 5 sxs down. (well was DV'ed). S.I.P. 500#. Closed in. RDMO. Following day checked well and it still had pressure. Dug out casing and cut off 6' below ground level.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD  BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES , CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES , NO \_\_\_\_\_  
Plugged through TUBING , CASING \_\_\_\_\_ Elevation: 2161 K.B.

I did [ X ] / did not [ ] observe the plugging.

Dennis L. Hamel  
(agent)

Form CP-2/3

INVOICED  
DATE JAN 13 1997  
INV. NO. 47330

HO.